

Earlier	Revised
<ul style="list-style-type: none"> <li>• Two 16' channel of 6"X3"</li> <li>• Frame size 10'X6' of 2" square pipe with 2 supports in between</li> <li>• Welded iron sheet size 8'X8' of 18 gauge thickness on both sides of frame</li> <li>• Display of messages on both sides of the hoarding with star quality 10 ounce flex</li> <li>• These hoardings are to be installed by the vendor at the selected 112 hospitals</li> <li>• The location of each hoarding has to be decided by respective SMO of the hospital.</li> <li>• After installation of hoarding ICTC staff of the hospital to be informed by said agency.</li> </ul>	<ul style="list-style-type: none"> <li>• Two channels size 16' of 6"x3". Three feet channel in depth in ground grouted with cement and concrete to make it solid.</li> <li>• Frame size 10'x8' from the top notch of the channel, 2" square pipe with 3 supports each side.</li> <li>• GI iron sheet size 8'X8' of 18 gauge thickness on both sides of the frame fixed with riveting maintaining to be started from top.</li> <li>• Display of messages on both sides of the hoarding with star quality (10 ounce flex)</li> <li>• These hoardings are to be installed by the vendor at the selected 112 hospitals.</li> <li>• The location of each hoarding has to be decided by respective SMO's of the hospitals.</li> <li>• After installation of hoarding, ICTC staff of that hospital to be informed by the said agency.</li> </ul>